

Hazardous Materials Abatement at  
Fullerton Union High School  
Culinary Arts Classroom  
Bid #0910-07

ADDENDUM No. 1  
February 26, 2010

**Fullerton Union High School – CTE – Culinary Arts – Building “H”**

The following changes, deletions, revisions, clarifications, attachment or additions to the specifications shall apply to the Fullerton HS – CTE – Culinary Arts – Building H. All other conditions shall remain as documented. **Respondents shall acknowledge receipt of addendum on the Bid Form.**

**Item 1.**

Clarification/revision:            Required Licensed

Contractor shall be licensed by the State of California, Contractors State License Board and be registered to perform asbestos related work with the Division of Occupational Safety and Health, Department of Industrial Relations. At a minimum contractor shall hold the following license classifications, training, and certifications:

1.    B License with ASB - Asbestos Certification

All removal and disturbance of asbestos-containing materials shall be performed by an asbestos abatement contractor, using 32-hour asbestos certified workers (Asbestos Worker trained as outlined in 40 CFR 763). Abatement contractor's workforce shall be supervised by experienced persons trained, knowledgeable and qualified in the techniques of asbestos abatement, handling and disposal of asbestos-containing and/or asbestos-contaminated materials, and the subsequent cleaning of contaminated areas, including, at a minimum, Competent Person/Contractor Supervisor training as outlined in 40 CFR 763.

2.    All removal and disturbance of lead-based containing materials shall be performed by a state-licensed contractor, using CDPH-certified workers with at least one CDPH-certified Supervisor. All removal and disturbance of lead-containing materials (not meeting the definition of "lead-based") as defined in 8 CCR 1532.1, shall be performed by a state-licensed contractor, using lead-trained workers with certification of training meeting the requirements of 8 CCR 1532.1. Abatement contractor's workforce shall be supervised by experienced persons trained, knowledgeable and qualified in the techniques of lead abatement, handling and disposal of lead-containing and/or lead-contaminated materials, and the subsequent cleaning of contaminated areas.

3.    Contractor shall utilize employees with HAZWOPER training, as outlined in 29 CFR 1910.120 and 8 CCR 5192, when handling all "other" hazardous materials, including fluorescent light ballasts and tubes, mercury switches, refrigerants, batteries, and the like.

**Item 2.**

Revision: Project Start Schedule

1. Project Start Date: June 1, 2010  
Project Duration: 1 Week – 1 Phase

The CTE – Culinary arts project will not be divided into phase as previously intended.  
ALL WORK is scheduled to commence on June 1, 2010 with a 1 week completion  
Schedule ending on June 7, 2010. (Inclusive of clearance sampling and tear down)

**Item 3.**

Attachment: Project Demolition Plans

1. Attached Project Demolition Plans
  - a. Sheet A-2.0 – Demolition Floor Plan, Floor Plan, Demolition Reflected Ceiling, Reflected Ceiling Plan
  - b. Sheet A-4.0 – Roof Plan, Partial Basement Plan, Roof Framing Plan, Typical Details
  - c. Sheet A-8.0 – Door & Finish Schedule, Basement Floor Plan & Typical Detail